

MODEL : HRP-600-15

OUTPUT FUNCTION TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	RIPPLE & NOISE	V1 : 150 mVp-p (Max)	I/P : 230VAC O/P : FULL LOAD Ta : 25°C	V1 : 60 mVp-p (Max)	P
2	OUTPUT VOLTAGE ADJUST RANGE	CH1 : 13.5 V~ 18 V	I/P : 230 VAC I/P : 115 VAC O/P : MIN LOAD Ta : 25°C	13.052 V~ 19.040 V / 230 VAC 13.046 V~ 19.040 V / 115 VAC	P
3	OUTPUT VOLTAGE TOLERANCE	V1 : 1 %~ -1 % (Max)	I/P : 100 VAC / 264 VAC O/P : FULL/ MIN LOAD Ta : 25°C	V1 : 0.2 %~ -0.2 %	P
4	LINE REGULATION	V1 : 0.3 %~ -0.3 % (Max)	I/P : 100 VAC ~ 264 VAC O/P : FULL LOAD Ta : 25°C	V1 : 0.08 %~ -0.08 %	P
5	LOAD REGULATION	V1 : 0.5 %~ -0.5 % (Max)	I/P : 230 VAC O/P : FULL ~MIN LOAD Ta : 25°C	V1 : 0.04 %~ -0.04 %	P
6	SET UP TIME	230VAC : 1000 ms (Max) 115 VAC : 2500 ms (Max)	I/P : 230 VAC I/P : 115 VAC O/P : FULL LOAD Ta : 25°C	230VAC/ 436 ms 115VAC/ 872 ms	P
7	RISE TIME	230VAC : 50 ms (Max) 115VAC : 50 ms (Max)	I/P : 230 VAC I/P : 115 VAC O/P : FULL LOAD Ta : 25°C	230VAC/ 19 ms 115VAC/ 20 ms	P
8	HOLD UP TIME	230VAC : 16 ms (TYP) 115VAC : 16 ms(TYP)	I/P : 230 VAC I/P : 115VAC O/P : FULL LOAD Ta : 25°C	230VAC/ 24 ms 115VAC/ 18 ms	P
9	OVER/UNDERSHOOT TEST	< ±5%	I/P : 230 VAC O/P : FULL LOAD Ta : 25°C	TEST : < 5 %	P
10	DYNAMIC LOAD	V1 : 1500 mVp-p	I/P : 230 VAC O/P : FULL /Min LOAD 90%DUTY/1KHZ Ta : 25°C	863 mVp-p	P

### INPUT FUNCTION TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	INPUT VOLTAGE RANGE	85VAC~264 VAC	I/P : TESTING O/P : FULL LOAD Ta : 25°C	55 ~264V	P
			I/P : LOW-LINE-3V= 97 V HIGH-LINE+15%=300 V O/P : FULL/MIN LOAD ON : 30 Sec . OFF : 30 Sec 10MIN ( AC POWER ON/OFF NO DAMAGE )	TEST : OK	
2	INPUT FREQUENCY RANGE	47HZ ~63 HZ NO DAMAGE OSC	I/P : 100 VAC ~ 264 VAC O/P : FULL~MIN LOAD Ta : 25°C	TEST : OK	P
3	POWER FACTOR	0.93 / 230 VAC(TYP) 0.99 / 115 VAC(TYP)	I/P : 230 VAC I/P : 115 VAC O/P : FULL LOAD Ta : 25°C	PF= 0.959 / 230 VAC PF= 0.995 / 115 VAC	P
4	EFFICIENCY	88% (TYP)	I/P : 230 VAC O/P : FULL LOAD Ta : 25°C	89.2%	P
5	INPUT CURRENT	230V/ 3.6 A (TYP) 115V/ 7.6 A (TYP)	I/P : 230 VAC I/P : 115 VAC O/P : FULL LOAD Ta : 25°C	I = 3.32 A/ 230 VAC I = 6.59 A/ 115 VAC	P
6	INRUSH CURRENT	230V/ 70 A (TYP) 115V/ 35 A (TYP) COLD START	I/P : 230 VAC I/P : 115 VAC O/P : FULL LOAD Ta : 25°C	I = 70 A/ 230 VAC I = 35 A/ 115 VAC	P
7	LEAKAGE CURRENT	< 1.2 mA / 240 VAC	I/P : 264 VAC O/P : Min LOAD Ta : 25°C	L-FG : 0.63 mA N-FG : 0.62 mA	P

### PROTECTION FUNCTION TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	OVER LOAD PROTECTION	105 %~ 135 %	I/P : 230 VAC I/P : 115 VAC O/P : TESTING Ta : 25°C	117%/ 230 VAC 117%/ 115 VAC Constant current limiting, recovers automatically after fault condition is removed	P
2	OVER VOLTAGE PROTECTION	CH1 : 18.8V~ 21.8 V	I/P : 230 VAC I/P : 115 VAC O/P : MIN LOAD Ta : 25°C	20.72 V/ 230 VAC 20.83 V/ 115 VAC Shut down Re- power ON	P
3	OVER TEMPERATURE PROTECTION	SPEC : Shut down o/p voltage, recovers automatically after temperature goes down	I/P : 230 VAC O/P : FULL LOAD	O.T.P. Active Shut down o/p voltage, recovers automatically after temperature goes down	P
4	SHORT PROTECTION	SHORT EVERY OUTPUT 1 HOUR NO DAMAGE	I/P : 264 VAC O/P : FULL LOAD Ta : 25°C	NO DAMAGE Constant current limiting, recovers automatically after fault condition is removed	P

### CONTROL FUNCTION TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	DC OK SIGNAL	PSU turn on : 3.3 ~ 5.6V; PSU turn off : 0 ~ 1V	I/P : 230 VAC O/P : FULL LOAD Ta : 25°C	PSU turn on : 5.187 V PSU turn off : 0 V	P
2	REMOTE SENSE	>0.5V	I/P : 230 VAC O/P : FULL LOAD Ta : 25°C	> 0.5V	P
3	FAN ON/OFF control test	----	I/P : 230 VAC O/P : TESTING Ta : 25°C	> 34.3%LOAD FAN ON < 31.1%LOAD FAN OFF	P



### SAFETY TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	WITHSTAND VOLTAGE	I/P-O/P : 3 KVAC/min I/P-FG : 2 KVAC/min O/P-FG : 0.5 KVAC/min	I/P-O/P : 3.6 KVAC/min I/P-FG : 2.4 KVAC/min O/P-FG : 0.6 KVAC/min Ta : 25°C	I/P-O/P : 5.49 mA I/P-FG : 4.59 mA O/P-FG : 3.69 mA NO DAMAGE	P
2	ISOLATION RESISTANCE	I/P-O/P : 500VDC>100MΩ I/P-FG : 500VDC>100MΩ O/P-FG : 500VDC>100MΩ	I/P-O/P : 500 VDC I/P-FG : 500 VDC O/P-FG : 500 VDC Ta : 25°C /70%RH	I/P-O/P : 30 GΩ I/P-FG : 30 GΩ O/P-FG : 30 GΩ NO DAMAGE	P
3	GROUNDING CONTINUITY	FG(PE) TO CHASSIS OR TRACE < 100 mΩ	40 A / 2min Ta : 25°C / 70%RH	11 mΩ	P
4	APPROVAL	TUV : Certificate NO : R 50153202 UL : File NO : E183223			P

### E.M.C TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	HARMONIC	EN61000-3-2,-3 CLASS A	I/P : 230 VAC/50HZ O/P : FULL LOAD Ta : 25°C	PASS	P
2	CONDUCTION	EN55022 CLASS B	I/P : 230 VAC (50HZ) O/P : FULL/50% LOAD Ta : 25°C	PASS Test by certified Lab	P
3	RADIATION	EN55022 CLASS B	I/P : 230 VAC (50HZ) O/P : FULL LOAD Ta : 25°C	PASS Test by certified Lab	P
4	E.S.D	EN61000-4-2 INDUSTRY AIR : 8KV / Contact : 4KV	I/P : 230 VAC/50HZ O/P : FULL LOAD Ta : 25°C	CRITERIA A	P
5	E.F.T	EN61000-4-4 INDUSTRY INPUT : 2KV	I/P : 230 VAC/50HZ O/P : FULL LOAD Ta : 25°C	CRITERIA A	P
6	SURGE	IEC61000-4-5 INDUSTRY L-N : 2KV L,N-PE : 4KV	I/P : 230 VAC/50HZ O/P : FULL LOAD Ta : 25°C	CRITERIA A	P
7	Test by certified Lab & Test Report Prepare				

### M.T.B.F & LIFE CYCLE CALCULATION

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	CAPACITOR LIFE CYCLE	HRP-600-24 : SUPPOSE C 106	IS THE MOST CRITICAL COMPONENT I/P : 230VAC O/P : FULL LOAD Ta= 25 °C LIFE TIME= 2024763 HRS I/P : 230VAC O/P : FULL LOAD Ta= 50 °C LIFE TIME= 232873.8 HRS		P
2	MTBF	Conducted by Parts Stress Analysis Prediction 1333.6K hrs min. Telcordia SR-332 (Bellcore) ; 140.7K hrs min. MIL-HDBK-217F (25°C)			P
3	Ongoing Reliability Test	I/P : 230VAC O/P : FULL LOAD TA=50°C Demonstration Mean Time Between Failure : 50,000 hours			P

### COMPONENT STRESS TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	Power Transistor ( D to S) or (C to E) Peak Voltage	Q3 Rated 20.7A/600V	I/P : High-Line +3V = 267 V O/P : (1)Full Load Turn on (2) Output Short Ta : 25°C	(1) 476 V (2) 498 V	P
2	Diode Peak Voltage	Q100 Rated 80A/75V  Q103 Rated 80A/100V	I/P : High-Line +3V = 267 V O/P : (1)Full Load Turn on (2)Output Short Ta : 25°C	(1) 67.6 V (2) 68.6 V  (1) 96.8 V (2) 94 V	P
3	Input Capacitor Voltage	C5 Rated 470u/400V 105°C	I/P : High-Line +3V = 267 V O/P : (1)Full Load Turn on /Off (2) Min load Turn on /Off (3)Full Load /Min load Change Ta : 25°C	(1) 377 V (2) 384.1 V (3) 384.2 V	P
4	Control IC Voltage Test	U1 Rated 10V~20V	I/P : High-Line +3V = 267 V O/P : (1)Full Load Turn on /Off (2) Min load Turn on /Off (3)Full Load /Min load Change Ta : 25°C	(1) 14.113 V (2) 14.248 V (3) 14.248 V	P
5	P.F.C Transistor ( D to S) or (C to E) Peak Voltage	Q1 Rated 20A/500V	I/P : High-Line +3V = 267 V O/P : (1)Full Load Turn on (2) Output Short Ta : 25°C	(1) 488 V (2) 432 V	P

TEST RESULT	TESTER	APPROVAL
PASS	SANFORD SU	VINCENT TSENG

2003/12/12 A50-F023